

**SURVEY & REMONUMENTATION**

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

Chippewa County Remonumentation Corner

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE 93 DEC 29 AM 10: 25

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

*J. Roger Malott*  
REGISTER OF DEEDS

For corners in	Located In:	Corner Code #
Chippewa (County)		
1. Public Land Survey	T <u>47N</u> R <u>1W</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-13) South 1/4 Corner of Section 31 (T47N-R1W)

1840: William A. Burt, D.S.

Set post.

40" Pine N30°W 12 links

1991: Ronald R. Bischer, L.S. 22428

Survey dated 11/11/91, Set PK nail for 1/4 Corner.

Power Pole S66°W 109.25'

6" Spruce N27°W 65.10'

Centerline Road North 2.50'

North 1/4 Corner Section 6 (1/2" rod) N70°E 9.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

It appears the Bischer PK nail was set by Proportionate Measurement, on line between the Southwest and Southeast corners of Section 31. This position falls South of the existing Township line as previously monumented for Section 6. We used the standard corner 31/32 and extended a line thru the North 1/4 corner of Section 6 to a point North of the PK nail (2.82'). This method places the standard corner 31/32, the North 1/4 corner of Section 6 and the South 1/4 corner of Section 31 all on a straight line. This creates a slight angle (07') at the South 1/4 corner of Section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap in the centerline of Six Mile Road.

Witnesses:

4" White Birch	N24°E	70.99'
North 1/4 Corner Section 6	East	8.94'
Power Pole (E 100)	S69°E	155.30'
Power Pole (E101)	S63°W	110.78'
4" Spruce	N27°W	62.56'
1/2" Iron	North	30.15'

Signed by William L. Karr

Date 12/23/93

Surveyor's Michigan License No. 27450



NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.