

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--|---------------|
| Chippewa <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>47</u> N R <u>1</u> W | <u>D-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling In Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property In Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
28 FEB 96 4:38 P.M. RECEIPT# 459
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/09, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | ● | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

D-11 1/4 Corner Common to Sections 29 & 32, Town 47 North, Range 1 West
1845 - Original ties (James Mullett): Spruce 6, S43°E 19 links - Spruce 6, N46°W 15 links.
1987 - William L. Karr, P.S. 27450, liber 9, page 157, Chippewa County recorded corners. Corner re-established by single proportionate measurement. Witnesses to 3/4" I.D. pipe with L.S. cap #27450 in south bank of ditch, 20 feet north of centerline of 5 Mile Road: 10" Tamarack, N15°W 51.35' - 9" White Birch, S10°W 58.88' - Power Pole (E72/454/17), N77°W 117.31'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 3/4" iron pipe with cap #27450 in ditch line, approximately 20 feet north of the centerline of east-west asphalt road (5 Mile Rd). Also found birch and power pole witnesses as called for in LCRC liber 9, page 157. Corner is mid-way on line between recovered Section corners east and west. Accepted corner as found and established additional witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" I.D. iron pipe with plastic cap #27450 in the ditch line, approximately 20 feet north of the centerline of 5 Mile Road (asphalt). Witnesses:
MBT Pole (E72/454), N77°W 117.00'
4" White Birch, N32°W 60.93'
4" Tamarack, N50°E 58.55'
9" White Birch, S10°W 58.77'

Note: Distances are to a nail in the side of the witness object. Trees are blazed and painted.
Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date December 29, 1995

