

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 27 1995


LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in
Chippewa
(County)

Located In: _____ Corner Code #/

1. Public Land Survey T 47N R 1W E-9
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:30 P.M. RECEIPT# 1519
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on January 21, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9 Corner Common to Sections 20, 21, 28, & 29, T47N, R1W

Original ties to post: Fir 6, N55°W 08 links
White Pine 10, S55°E 17 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 (T47N, R1W)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a hole with remains of a wood post next to a blazed cedar stump. Set a 3/4" rebar and 3 1/4" aluminum Chippewa County in center of hole. Corner is 5282.39 feet from Section corner to the east, 5347.23 feet from Section corner to the north, and 5327.82 feet from Section corner to the south. Corner is approximately 120 feet northwest of the Algonquin cross-country ski trail.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 (T47N, R1W)

Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation approximately 120 feet northwest of ski trail. Witnesses:

- 5" Cedar, S58°E 9.34'
- 9" Cedar, N74°E 13.00'
- 8" Black Spruce, N16°E 9.47'
- 6" Cedar, S83°W 26.81'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters Date 10-25-94
Surveyor's Michigan License No. 33142