

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

SECTION

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T47N R1W	F-5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

BOOK **11** PAGE **55**

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 23 FEB 2000 3:15:30 PM Receipt #2117  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, William L. Karr, in a field survey on December 15, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-5) 1/4 Corner Between Sections 9 and 16, T. 47 N., R. 1 W.

- 1845 James H. Mullett set post in original survey.
  - 1947 Rudolph H. Larsen surveyed Plat of Lake Shore Subdivision, L.6, P.4, Chippewa County Plats. The plat shows a concrete monument at the 1/4 corner.
  - 1983 William L. Karr, P.S. 27450, recorded the corner, L.6, P.99, Chippewa County Corner Records. Found concrete monument matching plat monumentation.
- Witnesses: Pwr Pole N 81° E 83.90'      14" Aspen S 52° E 29.52'  
 Pwr Pole S 82° W 12.10'      Pwr Pole N 19° W 102.88'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-5) 1/4 Corner Between Sections 9 and 16, T. 47 N., R. 1 W.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Accepted the corner position as shown on the plat and recorded in 1983, however, concrete monument was dug out during subsequent road and ditch reconstruction. Re-established the corner from previous survey work in the area and one existing witness.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-5) 1/4 Corner Between Sections 9 and 16, T. 47 N., R. 1 W.

Corner is a 3/4" x 48" iron with an aluminum Chippewa County Remonumentation cap. The corner falls on the back slope of a ditch along the South side of 16<sup>th</sup> Ave, just East of the intersection of Lakeshore Dr.

- Witnesses:
- 12" White Birch N 41° E 88.92'
  - 8" Aspen S 32° W 25.70'
  - 12" White Birch S 69° W 38.36'
  - Power Pole 3458/G4/6 N 21° W 102.75' (existing witness)

Bearings are compass bearings, corrected for declination (7° W), all distances are to a nail and tag in the side of the witness object unless otherwise noted trees are not blazed.

Signed by William L. Karr  
 Surveyor's Michigan License No. 27450

Date 12-29-99

