

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970⁺ 7.00 LAND CORNER

For corners in

Chippewa

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 47N R 1W | F-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 2.00 MSSR
 28 FEB 96 4:40 P.M. RECEIPT# 459
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/20, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11 1/4 Corner Common to Sections 28 & 33, Town 47 North, Range 1 West
 1845 - Original ties (James Mullett): White Pine 24, S21°W 31 links - Fir 4, N35°W 15 links.
 1915 - Chippewa County Surveyor notes for Section 33 indicate a distance of 5380 feet on the north line, with an excess of 100 feet in the west 1/2 mile.
 1982 - William L. Karr, P.S. 27450, liber 6, page 134, Chippewa County recorded corners. Set 1/2" iron on line between Northeast and Northwest corners of Section 33, opposite a fence line to the north and south. Witnesses:
 Power Pole, S74°E 127.45' - Fence Post, SOUTH 34.89' - Power Pole, N32°W 61.86' - 8" Poplar, S10°W 74.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
 Found a 1/2" iron 6" below surface of east-west asphalt road (5 Mile Road), on line with fences north and south. Also found four witness objects as called for in LCRC recorded in liber 6, page 134. Placed a 3/4" rebar with a plastic Chippewa County Remonumentation cap at surface of asphalt pavement. Distance to Section corner west is 100 feet more than distance to Section corner east, which fits with above mentioned 1915 County Surveyor notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" rebar with a plastic Chippewa County Remonumentation cap approximately 5 feet south of the centerline of 5 Mile Road (asphalt), on line with fences north and south. Witnesses:
 Power Pole, S74°E 127.45' (Existing PK nail in side)
 Fence Post, SOUTH 34.89' (Existing PK nail in side)
 Power Pole, N32°W 61.86' (Existing PK nail in side)
 11" Poplar, S10°W 73.98' (Set nail/tag P.S. 33142 in side)

Note: Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
 Surveyor's Michigan License No. 33142

Date December 29, 1995

