

MAR 27 1995 CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------|------|-----|
| 1. Public Land Survey | T 47N | R 1W | G-8 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
28 FEB 96 4:40 P.M. RECEIPT# 459
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/15, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 Corner Common to Sections 21 & 22, Town 47 North, Range 1 West

1845 - Original corner established by James Mullett was a 6" Spruce.

1985 - James L. Fletcher, R.L.S. 19830, unrecorded LCRC, indicates set 1/2" iron using bearings and distance found in old survey notes by Carleton in the County Surveyor's office. No witnesses are shown.

1985 - Corner is shown on a certificate of survey and a section subdivision sketch by James L. Fletcher, R.L.S. 19830.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.

The corner as shown in above mentioned unrecorded LCRC and certificate of survey was apparently never monumented in the field. Established corner location from other found monumentation in Section 22 as shown by James L Fletcher. Fletcher determined the corner location using the record angle and distance from the east 1/4 corner of Section 22 as shown in Chippewa County Surveyor notes from the 1920's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a 3" aluminum Chippewa County Remonumentation cap.

Witnesses:

- 7" Tamarack, N33°E 32.12'
- 10" Tamarack, N82°E 45.81'
- 7" Tamarack, S82°E 59.97'
- 4" Tamarack, S49°E 12.86'

Note: Distances are to a nail/tag P.S. 33142 in the side of the tree. Trees are blazed and painted.
Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date December 29, 1995

