

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 AM 10: 25

For corners in
Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 47N R 1W H-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 11, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(H-13) South 1/4 Corner Section 34 (T47N-R1W)

Corner set by William Burt, DS, in August of 1840.

Birch 10"	N6½°E	60 links
Birch 8"	N22°W	68 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner. Corner was established on line and midway between the Southeast and Southwest corners of Section 34 in previous survey. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(H-13) Corner is a ½" x 24" pin with L.S. cap. Corner falls 3' ± South of the centerline of Six Mile Road.

Witnesses:

Wood Post (with Telephone Box)	N62°E	100.13'
Power Pole (E34)	S62°E	115.53'
Power Pole (E35)	S76°W	151.53'
6" Spruce	N84°W	183.02'
North ¼ Corner of Section 3	West	6.31'

Signed by William L. Karr Date 12/21/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

