

SURVEY & REMONUMENTATION

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 CHIPPEWA COUNTY
 STATE OF MICHIGAN

93 DEC 29 AM 10: 25

J. Roger Malott
 REGISTER OF DEEDS

For corners in

Chippewa
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>1W</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____


	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(J-13) South 1/4 Corner Section 35 (T47N-R1W)

- 1840: William A. Burt, D.S. - Set post.
- 1960: J.P. Smallwood, Michigan Highway Department.
 Recorded in Liber 3, Page 236 of the Chippewa County Corner Records. Found a 3/4" iron. Recorded as common.
- Telephone Pole N05°E 52.33'
- Power Pole S45°W 65.86'
- Iron Post South 42.93'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-13) This corner is being re-established as part of the Chippewa County Remonumentation Program.

Corner recorded by Smallwood was determined to be the North 1/4 corner of Section 2. The South 1/4 corner of Section 35 was placed midway between the Southwest and Southeast corners of Section 35 on a line extended from Standard Corner 34/35 through the existing North 1/4 corner of Section 2. This creates a slight angle (06') at the South 1/4 corner of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-13) Corner is a 3/4" x 3" rod with plastic "Chippewa County Remonumentation" cap in a drilled hole in the concrete of the overpass. The corner falls on the existing centerline of Six Mile Road.

Witnesses:

- 20" Burr Oak N64°E 290.10'
- East Edge of Concrete Overpass East 189.61'
- 30" Burr Oak S20°E 230.95'
- Power Pole (E-14) S58°W 216.87'
- North 1/4 Corner Section 2 West 10.92'
- West Edge of Concrete Overpass West 100.70'
- Guard Rail Post on Ext. of Fence to Northeast N70°W 104.70'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
 Distances are to a nail in side of witness objects unless noted.