

MAR 27 1996

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSIONER

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T47N R.1W

K-8

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

\$ 7.00 LAND CORNER

\$ 2.00 MSSR

28 FEB 96 4:44 P.M.

RECEIPT# 459

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Keith R. Waters, in a field survey on 12/07, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell 8-24 contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 Corner Common to Sections 23 & 24, Town 47 North, Range 1 West

1845 - Original ties (James Mullett): Birch 20, S47°W 07 links - Sugar 4, N53°E 14 links.


1955 - Bancroft Bufe, R.L.S. 6152, liber 2, page 124, Chippewa County recorded corners. Set 1" pipe 2 1/2 feet above ground in rock mound. Corner is at mid-point on line between section corners north and south.

1980 - William L. Karr, P.S. 27450, liber 4, page 385, Chippewa County recorded corners. Replaced found pipe with a 4" concrete monument. Witnesses: 4" Oak, S24°03'E 21.34' - U.S.A.F. Radar Base fence posts, S64°48'W 20.91 and N40°07'W 27.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 4" concrete monument with a plastic cap #27450, 1 foot above ground in a rock mound. Also found three witness objects as called for in LCRC liber 4, page 385.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 4" concrete monument with a plastic cap #27450, 1 foot above ground in a rock mound, 18 feet east of a north-south chain link fence on the west side of I-75. Witnesses:

6" Red Oak, S85°E 17.59' (Nail/tag P.S. 33142 in side)

7" Red Oak, S64°E 29.07' (Nail/tag P.S. 33142 in side)

10" Sugar Maple, S09°E 40.11' (Nail/tag P.S. 33142 in side)

5" Sugar Maple, S11°W 21.40' (Nail/tag P.S. 33142)

Steel Fence Post in N-S Chain Link Fence, S65°W 20.91' (Nail/tag #27450 in top)

Steel Fence Post in N-S Chain Link Fence, N40°W 27.19' (Nail/tag #27450 in top)

Note: Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters

Date December 29, 1995

Surveyor's Michigan License No. 33142