

MAR 27 1995 CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970: 7.00 LAND CORNER

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 1W K-10
 T R
 T R
 T R
 S T R
 S T R
 S T R
 S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

\$ 2.00 HSSR

28 FEB 96 4:45 P.M. RECEIPT# 459
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/11, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 Corner Common to Sections 25 & 26, Town 47 North, Range 1 West
 1845 - Original ties (James Mullett): Sugar 10, N76°W 21 links - Sugar 8, N49°E 29 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.
 Found no evidence of corner or its accessories. Re-established corner by single proportionate measurement between recovered Section corners 2628.81 feet north and 2628.81 feet south. Corner falls in an old east-west road bed at the split of right-of-way fences 60 feet apart.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in an old east-west road bed. Witnesses:

- Power Pole (E-8), N78°W 182.46'
- 5" Apple, S67°E 68.79'
- 8" Aspen, N72°E 62.69'
- Fence Post (East side of Gate), N36°W 38.20'

Note: Distances are to a nail/tag P.S. 33142 in the side of the witness object.
 Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
 Surveyor's Michigan License No. 33142

Date December 29, 1995