

SURVEY & REMONUMENTATION

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 CHIPPEWA COUNTY
 STATE OF MICHIGAN

93 DEC 29 AM 10:25

J. Roger Malott
 REGISTER OF DEEDS

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>47N</u> R <u>1W</u> | K-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number


4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, William L. Karr, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
(K-13) Standard Corner Common to Sections 35 & 36 (T47N-R1W)
1840: William A. Burt, D.S. - Set post.
 4" Maple N22½°E 11 links
 20" Birch N60°W 20 links
1960: J.P. Smallwood, Michigan Highway Department.
 Recorded as common in Liber 3, Page 236 of the Chippewa County Corner Records.
- | | | |
|--------------------------------|-------|--------|
| Power Pole | N40°W | 34.48' |
| Power Pole | S50°E | 65.50' |
| Northeast Corner Cyclone Fence | S05°W | 38.90' |



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(K-13) This corner is being re-established as part of the Chippewa County Remonumentation Program.

Corner recorded by Smallwood was determined to be Closing Corner 2/1. Standard Corner 35/36 was re-established record distance (7.92') East of the accepted Closing Corner 2/1 on a line extended from the South ¼ corner of Section 35 through the existing Closing Corner 2/1.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(K-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap and falls 1.0' North of the centerline of Six Mile Road.

Witnesses:

- | | | |
|---------------------------|-------|---------|
| Power Pole (126/1) | N80°E | 169.14' |
| Power Pole | S77°E | 149.95' |
| Corner (Metal) Fence Post | S10°W | 40.18' |
| Corner (Metal) Fence Post | S55°W | 69.61' |
| Closing Corner 2/1 | West | 7.92' |
| Power Pole (126/2) | N48°W | 39.55' |



igned by William L. Karr

Date 12/23/93

urveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
 Distances are to a nail in side of witness objects unless noted.