

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 AM 10:25

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>47N</u>	R	<u>1W</u>	<u>L-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

J. Roger Matthe
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William L. Karr, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(L-13) South 1/4 Corner of Section 36 (T47N-R1W)

1840: William A. Burt, D.S. - Set post.
12" Cedar North 50 links
8" Cedar N17°W 33 links

1914: County Surveyor notes tie into South 1/4 corner of Section 36 with drainage ditch survey on the North-South 1/4 line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-13) This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner. Found pipe on approximate centerline of Six Mile Road. Worked well with the right-of-way fences but not the East-West location. Established South 1/4 corner midway between the Southeast and Southwest corners of Section 36 using found pipe for latitude. Re-established position falls on centerline of old ditch to the North, consistent with the 1914 County Surveyor notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap on the approximate centerline of Six Mile Road.

Witnesses:

11" White Pine	N58°E	121.79'
1 1/2" Pipe	East	5.06'
12" Scotch Pine	S14°E	61.92'
4" Spruce	S17°W	46.76'
North 1/4 Corner Section 1	West	3.96'
"V" Notch in North End 40" C.M.P.	N12°W	25.83'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.

