

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Chippewa  
(County)

Located In:	Corner Code	##
T 47N R 1E	A-12	Same
T 47N R 1W	M-12	Corner
T _____ R _____		
T _____ R _____		
S _____ T _____ R _____		
S _____ T _____ R _____		
S _____ T _____ R _____		
S _____ T _____ R _____		

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:14

*J. Roger Malott*

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on OCTOBER 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-12) West 1/2 Corner Section 31

Original ties to post:	Cedar 8	S 60° W	23 links
	Spruce 8	N 46° W	36 links

1991: Keith Waters found iron pipe and accepted. Set 1/2" iron with cap #33142 at road surface (Liber 7, Page 350).

6" Spruce	N 02° W	49.43'
Power Pole	N 69° E	72.96'
5" Aspen	S 12° W	119.97'

- Only ties available

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(A-12) Found corner and all accessories as recorded in Liber 7, Page 350 of the Chippewa County Records. Accepted corner position as found.

SURVEY &  
REMONUMENTATION

JUL 26 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-12) Corner is a 1/2" iron with cap L.S. 33142.

Witnesses:

6" Spruce	N 02° W	49.43'
Power Pole	N 69° E	72.96'
5" Aspen	S 12° W	119.97'

(Only ties available)



Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.