

MAR 18 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

For corners in SECTION

Chippewa Located In: Corner Code #

1. Public Land Survey SAME CORNER { T 47N R 2E J-1 ✓  
 T 48N R 2E J-13  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

#7.00 LAND CORNER  
 #2.00 MSSR  
 21 JAN 1999 11:02:11 AM Receipt #13123  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 366

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Larry R. Rogers, in a field survey on November 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	K	L	M
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

(J-1) North 1/4 Corner of Section 2, Township 47 North, Range 2 East.


The original post was placed in 1842 by John Mullett. Found no mention of Corner in County Surveyor notes. In 1990, William L. Karr, P.S. 27450 found a 1" iron pin in East Shore Drive. Subsequently, Ron Bischer, P.S. 22428 re-established the corner the same distance East of the Northwest corner of Section 2 as the previously mentioned 1" iron pin, and on line with the remains of an old fence East of East Shore Drive.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-1) North 1/4 Corner of Section 2, Township 47 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1" iron pin and 1/2" Bischer iron. Considering that there is no available history to substantiate the position of the 1" iron pin, the County Peer Review Committee agrees that the Bischer 1/2" iron pin is harmoniously related to existing monumentation and is accepted as the best existing evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-1) North 1/4 Corner of Section 2, Township 47 North, Range 2 East.

Corner is a 1/2" iron pin 1.5 feet Westerly of the centerline of East Shore Drive.

Witnesses:

3" Elm	S86°E	28.93 feet
14" Maple	S50°E	27.08 feet
14" Maple	S46°W	75.25 feet
Utility Pole	N85°W	18.96 feet
1" iron pin	North	20.34 feet



Signed by \_\_\_\_\_

Date 30 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.