

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 47 N. X. R. 1 W.	G-6/
2. PROPERTY CONTROLLING IN SECTION 15	T. 47 N. X. R. 1 W.	3/
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-2, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-6 West 1/4 Corner of Section 15. O.B.T.'S. Hemlock 12, S64⁰W, 18 1ks. & Hemlock 8, N32⁰E, 20 1ks.

3 North 1/16 Corner on West side of Section 15. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-6 Corner set M.P.O.L. between the N.W. and S.W. Section corners of Section 15.

3 Corner set M.P.O.L. between the N.W. Section Corner and the West 1/4 Corner of Section 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 1" Pipe with Plastic R.L.S. Cap. 3 D.N.R. Monument.

8" W. Birch, N28⁰E, 52.1'
 6" W. Pine, East, 25.8'
 6" W. Pine, S09⁰E, 39.65'
 8" W. Pine, S16⁰W, 15.05'
 Corner buried in center line
 of trail.

Fence Corner (North and West), S21⁰E, 4.3
 6" Tamarack, S25⁰E, 61.5'
 8" Spruce, S75⁰W, 37.2'
 8" Tamarack, N23⁰W, 33.1'

SIGNED BY

Gerald L. Wiggins
 Gerald L. Wiggins

DATE 1-22-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

