

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 48 N.R. 6 W


Chippewa COUNTY

DESCRIPTION OF CORNER West 1/16 Corner between Secs. 7-18.

CORNER MONUMENT 1 1/2 x 30" Iron Pipe & 1" pipe with Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 11-13-69

WITNESSES TO CORNER..... 8" Jack Pine (W1/16 BT) S40°E 20.0'



9" Jack Pine (W1/16 BT) S48°W 8.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies in low Jack Pine stand. Corner is on a line brushed to the South.

This corner placed by proportionate measure and on a line between the section corners. 15.25 chains to the West and 1/4 Corner 10.90 chains to East. Both are corners placed from original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 12-31-69  
REGISTERED LAND SURVEYOR