

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 6W	G6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 09/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 15 and 16. 1849 - Established by Wells Burt, Deputy Surveyor. Set cedar post. W.Pine 14" N30W 13 links, W.Birch 9" S22E 10 links. 1952 - Remonumented by Dean C. DeLaMater RLS, " This corner was pointed out to me by B.McTiver, District Forester, of Newberry. One original B.T. still in place, fair condition". Set 1" pipe with 4" brass cap. 10" J.Pine N26W 97 links, 9" J.Pine S46E 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the 1952 monument in good condition and at record bearing and distance from the 1952 NBTs. The J.Pine NW is in good condition, the J.Pine SE is standing dead. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. The original BTs were not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 15" J.Pine N21W 64.1' mrkd "1/4S" 1952 NBT
 9" J.Pine N12E 18.4' mrkd "1/4S NBT"
 10" Maple S20E 10.6' do
 10" W.Pine N88W 47.03' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/26/2010
 Surveyor's Michigan License No. 33986