

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 6. W. . .

----- Chippewa ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 15-16-21-22 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 9" W. Pine S 49° E 19 links
"S 22 NBT"

5" Jackpine N 43° E 46 1/2 links

6" Jackpine "S 15 NBT"
N 15° W 57 links

"S 16 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner as perpetuated by Marcus Schaff, Reg. Surveyor.

Found two iron pipes in ground surrounded by broken brick.

Location post 2 rods south of corner.

Corner lies in intersection of roads, NW-SE-SW.

No evidence of original B.T.s. Apparently removed in road construction.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/14/52
REGISTERED LAND SURVEYOR