## MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

## LAND CORNER RECORD

T. 49 NR 6-7 W

·	_		Chippewa	COUNTY
DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 18.				
DESCRIPTION OF CORNER	MONUMENT_I"	Pipe with 4" I	Brass Cap.	
WITNESSES TO CORNER 8" Jack Pine _ S 37 W. 27 Links _ (1/4 S NBT)				
	9" Jack Pine	S 66_E, _45 L	inks (1/4 S	N <u>B</u> T)
DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.				
This corner was replaced. Found wood post in place with Jack Pine stump bottoms bearing S 472 W, 23 Links and N 58 W, 26 Links.				
Checked south 6.92 chains to possible line tree, Jack Pine, down with old blazes.				
Old lines running north, south and west from corner.				
Placed location poster North on Road.				
This corner was placed and witnessed with J. Kutchera, Assistant, and L. Rubick, Assistant, on 23 June 1958.				
SURVEYORS SEAL				
		1.11	191	ekler
<del>.</del>		Silly	Puelel on	Cheles