

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Chippewa COUNTY  
T 49N R 6W

DESCRIPTION OF CORNER 1/4 Corner on North side Sec. 3

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7-14-71

WITNESSES TO CORNER..... 15" W. Pine (1/4 S 3 BT) S78°E 20.8'



9" W. Birch (1/4 S 3 BT) S35°W 17.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed on the township line and midway bet. Closing corners, 1/2 mile to East and West.

Note: This corner was not set in the original survey.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler

DATE

9-28-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68