

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 49-50N R 6W

DESCRIPTION OF CORNER Meander Corner bet. Secs. 2-34, on the Township Line, at East shore of Whitefish Bay.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 7-14-71

WITNESSES TO CORNER..... 8" W. Birch (NET) S19°W 16.9'



9" W. Birch (NET) S81°E 16.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This meander corner re-established by proportionate distance and on the township line. Corner located on an old ridge, which appears to be a former shoreline. Bearing of this ridge agrees with record meander note bearings.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

9-28-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68