

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N. R. 6W


Chippewa COUNTY

DESCRIPTION OF CORNER Closing corner bet. Secs. 5-6, on the 5th correction line

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6-13-69

WITNESSES TO CORNER..... 9" Red Pine (S5 NBT) S10°E 30.0'



5" Red Pine (S6 NBT) S50°W 16.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found 7" jack pine, N62°E, 13.0' tree has been scribed "1941"

Corner replaced from W. Pine witness, bearing, N60°E, 47 links. Found remains of lower face with scribe marks "BT". A hemlock stump bottom bears N34½°W, 70 links for the second witness.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-29-69
REGISTERED LAND SURVEYOR