

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA COUNTY

*3 corners*

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> <sup>N.</sup> <del>S.</del> , R. <u>6</u> <sup>W.</sup> <del>E.</del>	<u>G-3; G-2; G-4;</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____, S. _____, R. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, S. _____, R. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS., do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11/13/75, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corners set by Wells Burt, D.S. in 1849.**

G-3; Sec. Cor. 3-4-9-10. Bearings were:  
Spruce 6", S70E, 53 Lks. and Spruce 7", N52W, 66 Lks.

G-2; Quarter Cor. bet. Secs' 3-4. Bearings were:  
W.Birch 5", S85E, 19 Lks. and W.Birch 7", S35W, 19 Lks.

G-4; Quarter Cor. bet. Secs' 9-10. Bearings were:  
Cedar 8", S20W, 56 Lks. and Cedar 8", N56E, 20 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-3; Corner re-established by Single Proportionate Measure bet. Cors, 1 mile North and 1½ miles South.

G-2; Corner re-established by S.P.M., and on line bet. two Sec. Cors.

G-4; Corner re-established midway and on line bet. two Sec. Cors.  
Corner lies in a flooded Beaver Dam, many Cedars but none can be identified as witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" Pipe with 4" Aluminum Cap, at all Corners.

G-3; New Bearings:  
6" Cedar, S62W, 20.38 and 6" Cedar, N1W, 77.08.

G-2; New Bearings:  
12" W.Birch, N62E, 11.7' and 12" S.Maple, S22E, 31.0'.

G-4; Bearings:  
No Witness Trees available.

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 9/28/76

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_