

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 6 W.	B-7
2. PROPERTY CONTROLLING IN SECTION 19	T. 49 N. R. 6 W.	10-Sec. 19
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-15, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-7 Quarter Corner bet. Sec's. 18-19, set by Wells Burt, D.S. in 1849. Bearings were: Spruce Pine 10", N32°W, 56 lks. and Spruce Pine 8", S40°E, 38 lks.

10-Sec. 19 South 1/16 Corner on West side of Section 19.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-7 Re-established corner on line and by single proportionate measure between two original section corners. Area burned badly, no old stumps remain.

10-Sec. 19 Placed corner midway and on line between Sec. Cor. to South and 1/4 Cor. to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at both corners. Bearings:

B-7 16" R. Pine, N86°W, 60.0' & 9" J. Pine, N45°E, 8.8' & 8" J. Pine, S42°E, 33.4'.

10-Sec. 19 8" J. Pine, S80°W, 3.7' & 8" J. Pine, S62°E, 8.2' & 8" J. Pine, N26°E, 13.7'.

SIGNED BY

Billy D. Buckler

DATE 7-15-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

