

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>49</u> N. <u>6</u> E. <u>W.</u>	A-8
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	, T. <u>49</u> N. <u>6</u> E. <u>W.</u>	<u>8-Sec.19, 11-Sec.19</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-15, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-8 1/4 Cor. on West side of Section 19, set by Austin Burt, D.S. in 1840. Bearings were: Pine 9", S74°W, 09 lks. & Aspen 8", N68°W, 16 lks.
- 8-Sec.19 West 1/16 Corner of Section 19.
- 11-Sec.19 South-West 1/16 Corner of Section 19.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-8 Replaced corner midway and on line bet. two Sec. Cors. Found a J. Pine stump bottom, S74°W, 9 lks., no identifying marks.
- 8-Sec.19 Placed corner on line and by a mean proportion of the West 1/2 miles, on the North and South sides of section.
- 11-Sec.19 Placed corner at intersection of lines quartering the SW Quarter Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at all corners. Bearings:

- A-8 14" Red Pine, S48°E, 19.6' & 14" J. Pine, N7°E, 8.9' & 14" J. Pine, S30°W, 12.3' Corner lies 30' South of an old telephone line.
- 8-Sec.19 8" J. Pine, N4°E, 5.0' & 9" J. Pine, S80°E, 16.4' & 10" J. Pine, S54°W, 9.3'.
- 11-Sec.19 16" W. Pine, N1°W, 42.6' & 16" W. Pine, S50°E, 41.1' & 12" R. Pine, S60°W, 13.9'

SIGNED BY _____

Billy D. Buckler

DATE 7-15-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

