

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>49</u> N. <u>6</u> E. <u>W.</u>	B-9, A-9, B-10
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>49</u> N. <u>6</u> E. <u>W.</u>	8-Sec. 30
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. <u>W.</u>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-12, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-9 1/4 Corner bet. Sec's. 19-30, set by Wells Burt, D.S. in 1849. Bearings were:
Spruce Pine 7", N55°W, 40 lks. & Spruce 7", S69°E, 41 lks.
- A-9 Sec. Cor. 19-30, on West Township Boundary. Bearings were:
Tam. 8", S29°W, 29 lks. & Spruce 12", N81°W, 55 lks.
- B-10 Center Corner of Section 30, T49N R6W.
- 8-Sec.30 West 1/16 Corner of Section 30.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Found 3/4" Iron Pipe at corner, believed set by Combine-Locke Land Co. Position checks well with other corners in area.
- A-9 Found 3/4" Iron Pipe in place. Position checks with other corners in area.
- B-10 Found 3/4" Iron Pipe in place; one of several pipes at interior corners of this section.
- 8-Sec.30 Found 1" Iron Pipe in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at B-9, A-9, B-10. Monument 8-Sec.30 1" pipe. Bearings:

- B-9 8" J. Pine, S87°W, 10.1' & 4" J. Pine, S10°E, 18.2'
- A-9 12" R. Pine, N7°E, 29.3' & 18" R. Pine, N70°E, 22.1' & 8" Spruce, S85°W, 17.3'.
- B-10 6" J. Pine, East, 10.5' & 6" J. Pine, S16°W, 27.0' & 6" J. Pine, N71°W, 21.4'.
- 8-Sec.30 4" J. Pine, N24°E, 26.7' & 5" J. Pine, N87°E, 49.8'.

SIGNED BY Billy D. Buckler DATE 7-14-81

Billy D. Buckler 8887

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

