

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. 6 W.	H-3
2. PROPERTY CONTROLLING IN SECTION 10 _____	T. 49 N. 6 W.	2-Sec.10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-24, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-3 1/4 Cor. bet. Sec's. 3-10, set by Wells Burt, D.S. in 1849. Bearings were:
W. Birch 4", West, 2.29 chs. and Y. Birch 8", East, 8.55 Chs.
- 2-Sec.10 East 1/16 corner on North side of Section 10.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-3 Re-established corner midway bet. two section corners. Found no evidence of original corner or evidence of use.
- 2-Sec.10 Established corner midway bet. Sec. Cor. to East and 1/4 Corner to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at both corners.

- H-3 New Bearings: 6" Cedar, N1°W, 21.3' and 6" Cedar, S73°E, 5.9'.
- 2-Sec.10 Bearings: 4" Cedar, N56°E, 32.0' & 6" Cedar, N26°E, 16.0' & 6" Spruce, N84°W, 10.0'

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

