

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>49</u> ^{N.} _{S.} , R. <u>6</u> ^{E.} _{W.}	H-5
2. PROPERTY CONTROLLING IN SECTION <u>15</u>	, T. <u>49</u> ^{N.} _{S.} , R. <u>6</u> ^{E.} _{W.}	2-Sec.15
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-5 1/4 Cor. bet. Sec's. 10-15, set by Wells Burt, D.S. in 1849. Bearings were: Tam. 6", S22°W, 40 lks. & Tam 6", N82°E, 34 lks.

2-Sec.15 East 1/16 Corner on North side of Section 15.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-5 Corner restored by extending a strait line from original section corner 9-10-15-16 East thru an original W. Pine Line tree at 2,452.87' (record = 37.12 chs.) and 190.1' East of the line tree. Found no original Tam. bearings:

2-Sec.15 Placed corner on line bet. 1/4 corner to West and Meander Corner to East and at proportionate distance East of the 1/4 Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at both corners.

H-5 New Bearings: 6" Cedar, South, 4.4' and 10" Cedar, S88°E, 16.7'.

2-Sec.15 Bearings: 6" Cedar, N68°W, 8.8' and 6" Cedar, N11°E, 22.5'.
Corner lies in West root of a clump of four Maples.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

