

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
Chippewa Co. 1 Corner

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> N. <u>X</u> , R. <u>6</u> E. <u>W.</u>	<u>I-3</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner 2-3-10-11, set by Wells Burt, D.S. in 1849. Bearings were:  
W. Birch 14", N83°W, 46 lks. and W. Pine 18", S16°E, 96 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-established corner at record distance from section corner one mile West and a proportionate distance from the closing corner one mile North and a County Surveyors Monument on line between sections 10 and 15, one mile South. Corner placed 82.67' South of the South line of the Betsy Plat, which was not the Section Line, although the Plat is recorded as such. This Section Corner set for the purpose of control to sub-divide Sections 3 and 10. I find no conflict in this location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Buried a 36" T-Iron in Blacktop Road, at corner, being 6.9' West of Center Line.  
New Bearings: 8" W. Birch, S60°W, 54.7' and 6" W. Pine, N25°W, 96.3'.

SIGNED BY

Billy D. Buckler  
Billy D. Buckler

DATE

7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO.

8887

