

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. E. R. <u>6</u> E. W.	I-2, I-2A, I-2B
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-15, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-2 1/4 Cor, bet. Sec's. 2-3, set by Wells Burt, D.S. in 1849. Bearings were:  
Y. Pine 12", S70°W, 1.12 chs. & Y. Pine 10", N28°E, 1.78 chs.
- I-2A Point on E-W 1/4 line, Sec.3; 596.5' West of the 1/4 cor. bet. Sec's. 2 and 3; and 33.0' East of the center line of Wire Road.
- I-2B Point on E-W 1/4 line, Sec.2; 569.2' East of the 1/4 cor. bet. Sec's. 2 and 3, and on a sand ridge of Lake Superior shore.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-2 Restored corner by single proportionate measure bet. two Sec. Cors. Found no evidence of original corner but found stream to North agrees with record.
- I-2A Placed corner on the computed E-W 1/4 line, Section 3, while conducting a submerged lands survey, in sections 2, 3, and 11.
- I-2B Placed corner on the computed E-W 1/4 line, Section 2, by extending the E-W 1/4 line, Sec. 3 to the lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2 Placed 1" pipe with 4" alum. cap at corner. New Bearings: 18" W. Pine, S31°E, 38.4' & 8" Tamarack, S4°W, 22.9' & 14" J. Pine, N76°E, 53.4'.
- I-2A Placed 36" T-Iron at corner. Bearings: 24" W. Pine, N26°E, 120.95' & 18" W. Pine, S64°E, 56.2'.
- I-2B Placed 36" T-Iron at corner on sand ridge, on shore of Lake Superior. Bearings: 7" W. Birch, N74°W, 58.3' & 9" J. Pine, S30°W, 36.35'.

SIGNED BY \_\_\_\_\_

Billy D. Buckler  
Billy D. Buckler

DATE 7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

