

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>6W</u>	<u>67</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>22</u> T <u>49N</u> R <u>6W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(67) Corner common to Sections 15-16-21-22. 1957 - Position for the corner monumented by Billy D. Buckler RLS. Set 1" pipe with 4" brass cap perpetuating location of Marcus Schaff RLS, marked by two iron pipes and broken brick. Witnesses: 9" W.Pine S49E 19 links, 5" Jack Pine N43E 46.5 links, 6" Jack Pine N15W 67 links.  
 (3-Sec. 22) North 1/16 corner between Sections 21 and 22. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(67) Recovered a 1"ID iron pipe with plastic cap stamped #23521 (Gerald Wiggins, PS), at record bearing and distance from the 1957 NBTs W.Pine SE, now 20" dbh in good condition, and the Jack Pine NE, now a cut stump. The Jack Pine NBT NW has been removed by road construction and was not recovered. Left the monument in place and marked new bearing trees as described below.  
 (3-Sec. 22) Established the corner midway and on the section line between Section corner 1318.26' north and Quarter corner 1318.26' south. Found 1" iron pipe, not of record, N76W 2.5' distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(67) Found 1"ID I.pipe with plastic cap # 23521. Set measuring nails in: 20" W.Pine S46E 12.7' mrkd "S22" * 16" twin Oak N64W 52.6' mrkd "S16 NBT" 14" R.Pine N32E 26.55' "S15 NBT" 12" R.Pine S21W 42.05' "S21 NBT" Bearings are magnetic. Distances are to nail with tag. * denotes 1957 NBT.	(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" R.Pine S46W 19.92' mrkd "N1/16 BT" 6" R.Pine N34W 21.25' do 7" W.Birch N28E 17.85' do 10" W.Pine S71E 7.38' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/29/06