

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 7-SW


Ince & Chippewa COUNTY

DESCRIPTION OF CORNER Meander corner bet. Secs. 25030, on south side of Clark Lake

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-25-69

WITNESSES TO CORNER..... 9" Red Pine (MC NBT) S40°W 26.1'



7" B. Spruce " S65°E 31.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one probable witness tree; a green Red Pine bearing S35°E, 25 links. Found scar in proper position but couldn't identify any scribe marks. Found line of blazes to south. Also found other blazes facing the corner.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 3-2-70
REGISTERED LAND SURVEYOR