

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>49N</u> R <u>7W</u>	<u>E1</u>
	T <u>50N</u> R <u>7W</u>	<u>E13 (same corner)</u>
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 31 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E1) Corner common to Sections 4-5 T49N-R07W and Sections 32-33 T50N-R07W. 1840 - Established by Wm.A.Burt, Deputy Surveyor: "West on South side of Section 33 ...80.00 Set post corner of Sections 32 & 33. Birch 10 N62 1/2E 36 links, B.Oak 11 N38W 25 links". Oct. 24 1939 - Notes presumably of Marcus Schaaf RLS state: "Fd. Oak stp. in place and Y.Birch stump with 5 [illegible]. New bearings W.P. stp 32 N65W 10 links, W.P. stp 20 N84W 1.24, W.P. stp 16 N52W 79, W.P. bottom 36 N18W 106." 1985 record of a 1973 survey by Billy D. Buckler RLS states: "Set by myself 10-21-52. 10" J.Pine S75W 57 links. This corner was placed by myself in 1952 at corner located and perpetuated by Marcus Schaaf, RLS". 1" pipe with 4" brass cap. Added new witness 6" W.Pine S85W 51.3', 7" W.Birch N64E 20.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E1) Recovered the 1952 monument in good condition and at record bearing and distance from the 1973 witnesses of record. The W.Pine S85W is down and the W.Birch NE is in good condition. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E1) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:
 9" W.Birch N67E 20.9' w/open blazes *
 5" W.Pine N18E 28.8' mrkd "S33 NBT"
 6" W.Pine N05W 34.7' "S32 NBT"
 4" W.Pine S21W 14.0' "S5 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1973 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06

For the Michigan Department of Natural Resources, Office of Land and Facilities

