

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa

(County)

Located In:

Corner Code #

| | | |
|---------------------------------------|--------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>7W</u> | <u>E3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 11 2005

Stephan J. Szyszkoski

I, _____, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. 1849 - Established by Wells Burt, Deputy Surveyor. Set Spruce post corner of sections 4,5,8 & 9. BTs: Spruce 6 S22E 27 links, Maple 8 N47W 28 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) The original post and accessories were not recovered. Found and accepted a 1" ID iron pipe, set by persons unknown, said pipe being located S56W 12.4' from the double proportionate position for the corner between perpetuated original corners C3 5261.28' West (5258.88' GLO), E10 18,432.62' South (18,480.00' GLO), G3 5305.91' East (5282.64' GLO), and a recorded corner of long standing E2 2641.03' North (2640.00 GLO). Left the pipe in place and drove a cast aluminum MDNR tablet into the top of it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Found 1" ID I.pipe. Set 4" alum. MDNR cap on it. Set measuring nails in:
 10" J.Pine S50E 19.83' mrd "S9 NBT"
 10" Balsam N50E 10.25' "S4 NBT"
 8" Balsam N80W 15.0' "S5 NBT"
 4" Balsam S21W 8.75' "S8 NBT"
 Bearings are magnetic. Distances are to nail with tag.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | ● | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06