

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>7W</u>	<u>G2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		●	3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Oct 11 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G2) Quarter corner common to Sections 3 and 4. 1849 - Established by Wells Burt, Deputy Surveyor: "South corrected between Sections 3 & 4 ...39.65 Set Spruce post qr. section corner. Spruce 5 N50W 27 links, Cedar 12 S30E 18 links. ...79.65 Section corner". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G2) The original post and accessories were not recovered. Found a 1" ID iron pipe, placed by an unknown surveyor, said pipe being located 0.24' East of the Section line between G1 and G3 and 2.58' North of the position proportionate to the original record. Accepted same as the best available evidence of the position of the original corner. Left the pipe in place and drove an aluminum MDNR tablet into the top of it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G2) Fd 1" ID I.pipe. Set 4" alum. MDNR cap in top. Set measuring nails in:  
 16" W.Pine N37E 17.25' mrkd "1/4S NBT"  
 6" Balsam S55E 6.6' do  
 17" W.Pine S62W 31.6' do  
 5" Balsam N55W 25.0' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/21/06

For the Michigan Department of Natural Resources, Office of Land and Facilities