

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>7W</u>	<u>63</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 21 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20 \_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1849 - Established by Wells Burt, Deputy Surveyor: North between Sections 9 & 10 ...80.00 Set Spruce post corner of Sections 3,4,9, and 10. Spruce 7 S59E 4 links, Spruce 7 N19W 10 links. 1952 - Remonumented by Dean C. DeLaMater, RLS: "This corner was pointed out to me by B. McTiver, District Forester, of Newberry. One original B.T. still in place, poor condition". Set 1" Pipe with 4" brass cap. 7" Spruce S63W 16 links, 10" J.Pine N13E 11 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Found the 1952 monument in good condition, inside a 2" iron pipe, not of record, at record bearing and distance from the 1952 witness trees, now both rotting stumps. Left the monument in place and made new bearing trees, as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap in 2" ID iron pipe. Set measuring nails in:  
 5" W. Birch S70W 9.9'      mrdk "S9 NBT"  
 4" B. Spruce N36W 18.5'      "S4 NBT"  
 5" J. Pine N27E 19.9'      "S3 NBT"  
 6" B. Spruce S68E 18.6'      "S10 NBT"  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/21/06