

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|--------------------------|
| 1. Public Land Survey | T <u>49N</u> R <u>7W</u> | <u>I1</u> |
| | T <u>50N</u> R <u>7W</u> | <u>I13 (same corner)</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File Number

Jul 25 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T49N-R07W and Sections 34-35 T50N-R07W. 1840 - Established by Wm. A. Burt, Deputy Surveyor: "West on South side Sec. 35 ...80.00 Set post corner of Sections 34 & 35. Birch 10 N53W 31 links, Beech 10 N3W 25 links". 1959 - Re-monumented by Billy D. Buckler, RLS: "Replaced cor. as set by Marcus Schaaf, Reg. Surveyor. Found 2" pipe by school [sic - probably intended "Schaaf"] with wood slabs at location of both B.Ts". Set 1" pipe with 4" brass cap. 12" W.Pine South 03 links, 13" W.Pine N50E 35 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Recovered the 1959 monument in good condition and at record bearing and distance from the 1959 witnesses. The W.Pine South is in good condition, the W.Pine NE is standing dead. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set

- measuring nails in:
- 16" W.Pine South 2.1' mrkd "S2" *
 - 10" W.Pine S81E 8.25' mrkd "S2 NBT"
 - 9" Maple N79W 10.65' mrkd "S34 NBT"
 - 10" Maple N44E 14.75' mrkd "S35 NBT"

Bearings are magnetic. Distances are to nail with tag. * denotes 1959 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06

For the Michigan Department of Natural Resources, Office of Land and Facilities

