

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___ T ___ R ___ T ___ R ___	_____ _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S <u>4</u> T <u>49NR</u> <u>7W</u> S <u>4</u> T <u>49NR</u> <u>7W</u>	_____ <u>6</u> <u>14</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	14 Oct 26 2005 6 Oct 02 2005	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1							●						
2	6		5		4			3		2		1	
3							●						
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (6-Sec. 4) Northeast 1/16 corner, Sec. 4. Not established in the original survey.
- (14-Sec. 4) South 1/16 corner between Sections 3 and 4. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (14-Sec. 4) Established the corner midway and on line between Section corner 1320.86' South and Quarter corner 1320.86' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (6) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
12" J.Pine S88W 7.95' mrkd "NE1/16 BT"
6" Balsam S20W 13.9' do
12" J.Pine N45E 14.45' do
5" Balsam N40W 8.6' do
Fd. 1" pipe N15W 9.7' distant. Bearings
are magnetic. Distances are to nail
with tag. | (14) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
7" Balsam N51E 12.45' mrkd "S1/16 BT"
16" Hemlock S02W 18.4' do
12" Maple N81W 12.4' do
10" Hemlock N06E 34.45' do
Fd. 1" pipe S81E 2.72' distant.
Bearings are magnetic. Distances are to
nail with tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06

For the Michigan Department of Natural Resources, Office of Land and Facilities