

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S <u>4</u> T <u>49N</u> R <u>7W</u>	<u>7</u>
	S <u>3</u> T <u>49N</u> R <u>7W</u>	<u>1</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	1 Oct 27 2005	
	7 Oct 03 2005	

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4				3	2	1			
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 4) North 1/16 corner between Sections 3 and 4. Not established in the original survey. Found no subsequent record.
 (1-Sec. 3) West 1/16 corner between Section 3 T49N-R07W and Section 34 T50N-R07W. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 4) Established the corner on the Section line between corners G1 and G2 and 20 chains, proportionate to the original GLO plat, north of G2. The position for the corner is thus 1318.26' north of G2 (20.00 ch R) and 1295.19' south of G1 (19.65 ch R).
 (1-Sec. 3) Established the corner on the township line and midway between Section corner 1328.97' West and Quarter corner 1328.97' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Balsam S75E 21.8' mrkd "N1/16 BT" 6" Balsam S28E 24.55' do 6" Spruce S22W 29.77' do 3" Spruce S57W 10.92' do Fd. 1" pipe N68W 4.86' distant. Bearings are magnetic. Distances are to nail with tag.	(1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Maple S10E 0.92' mrkd "N1/16 BT" 20" W.Pine S64E 13.57' do 7" W.Pine N13W 14.6' do 9" twin Maple N75W 6.4' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06