

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa
 (County)

Located In:

Corner Code #

1. Public Land Survey T ___ R ___
 T ___ R ___
 T ___ R ___
 S ___ T ___ R ___
 S 4 T 49N R 7W 15
 S 4 T 49N R 7W 11
 S ___ T ___ R ___
 S ___ T ___ R ___

2. Property Controlling in Section
 3. Miscellaneous Property in Sec.
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims

11 Oct 26 2005
 15 Oct 18 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15-Sec. 4) West 1/16 corner between Sections 4 and 9. Not established in the original survey.
 (11-Sec. 4) Southwest 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 4) Established the corner midway and on the section line between monumented Section corner 1326.48' West and monumented Quarter corner 1326.48' East. The corner lies approximately 13' east of a NW-SE road.
 (11-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" J.Pine N40E 42.4' mrd "W1/16 BT" 5" J.Pine N45W 27.9' do 8" W.Birch S54W 28.1' do 7" W.Birch S02W 56.55' do	(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 12" J.Pine S87W 70.55' mrd "SW1/16 BT" 6" J.Pine S48W 43.1' do 16" W.Pine S37E 39.3' do 5" J.Pine S71E 76.35' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/21/06

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

