

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___ T ___ R ___ T ___ R ___	_____ _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S <u>4</u> T <u>49N</u> R <u>7W</u> S <u>4</u> T <u>49N</u> R <u>7W</u>	_____ <u>16</u> <u>9</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	9 Aug 29 2005 16 Oct 11 2005	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4	●	3		2		1	
3							●						
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (16-Sec. 4) East 1/16 corner between Sections 4 and 9. Not established in the original survey.
- (9-Sec. 4) East 1/16 corner, Sec. 4. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (16-Sec. 4) Established the corner midway and on the section line between monumented corner F3 1326.48' West and monumented corner G3 1326.48' East.
- (9-Sec. 4) Established the corner midway and on a straight line between Quarter corner G2 1323.00' East and Center of Section 4 (unmonumented) 1323.00' West.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |  |
|---|--|
| (16) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>10" W.Pine N17E 32.68' mrkd "E1/16 BT"<br>4" Maple East 29.15' do<br>5" Maple N80W 29.58' do<br>6" Maple N28W 3.05' do<br>Fd. a 1" pipe N30E 16.84' distant.<br>Bearings are magnetic. Distances are to nail with tag. | (9) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>5" Spruce S56E 4.1' mrkd "E1/16 BT"<br>8" J.Pine N29E 9.1' do<br>8" J.Pine N01E 15.62' do<br>7" J.Pine S78W 41.4' do<br>Fd. 1" pipe with 1.5" pipe adjacent S08W 17.4' distant. Bearings are magnetic. Distances are to nail with tag. |
|---|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/21/06

For the Michigan Department of Natural Resources, Office of Land and Facilities