

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 50 & 51 N.R. 5 W


Chippewa COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 5-6 T50N R5W & 31-32 T51N R5W

CORNER MONUMENT 2 1/2" X 28" Iron post with Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6/4/64 Frank J. Bray

WITNESSES TO CORNER..... 11" W. Pine (S32 BT) N65° 08' E, 117 1/2 Lks.



9" W. Pine (S5 BT) S19° 54' E, 141 1/2 Lks.

13" W. Pine (S6 BT) S82° 25' W, 149 1/2 Lks.

AND

12" W. Pine (S31 BT) N3 3/4° W, 140 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set by Surveyor for Bureau of Land Management, Department of Interior in 1959. Cap Marked-

T51N	R5W
S.31	S.32
S.6	S.5
T50N	

1959

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/18/1964
REGISTERED LAND SURVEYOR