

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50N N. R. 6W


Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side, Sec. 33, on 5th correction line

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6-16-69

WITNESSES TO CORNER..... 16" Red Pine (1/4 S 33 NBT) N43°W 24.6'



12" Red Pine (1/4 S 33 NBT) N36°E 6.3'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from two original witnesses, both W. Pine, bearing N4°E, 12 links and N62°W, 19 links. Both are stumps, burned and with evidence of lower face and notch.

Found no evidence of use.

Corner lies 40' south of a swamp and on high, pine land.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 8-29-69