

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 6 W


Chippewa COUNTY

DESCRIPTION OF CORNER Sec. Corner common to Secs. 26-27-34-35.

CORNER MONUMENT 1" pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 11-13-69

WITNESSES TO CORNER..... 12" White Pine (NBT) N26°W 36.6'



10" Cedar (NBT) S7°W31.0'

2" Iron pipe East 120.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner replaced at 3" Iron Pipe marking the Section Corner as well as a Plat Corner. Corner lies in the North-West Edge of a road intersection. Pipe has been pushed over by traffic and created a hazard as well as being subject to removal.

Buried the Department Marker along side this 3" pipe, below the surface to perpetuate this location.

Corner shown to me by E.A. Sainio, R.L.S., Newberry.  
Found 2" Iron Pipe 120.2" East of Corner on the lake shore.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 12-31-69  
REGISTERED LAND SURVEYOR