

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 6 W


Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 5 and 8

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 10/28/60 with G. Hamilton

WITNESSES TO CORNER....13" Red Pine (1/4S NBT) N 56° W 117 Links



7" Red Pine (1/4S NBT) S 48° E 81 Links

8" White Pine (1/4S NBT) S 33° W 81 Links

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was replaced from one Yellow Pine B.T. in excellent condition bearing N 44° E, 19 links. Tree is down but still green. Corner found by George Hamilton Assistant and L. Rubick, Aide. Placed location marker 9 chains North of corner on "wildcat" road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 14, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler