

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50. NR. 5-6. W.

Chippewa COUNTY

DESCRIPTION OF CORNER Section corner 6-7-1-12

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 15" W. Pine S 40° E 154 links
"S 7 NBT"

10" W. Pine S 14° W 199 links
"S 12 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from white pine (probable) B.T. bearing N 49° W 221 links.

Found 2" iron pipe and concrete monument with brass plate in place.

Checked east 7.10 chs. to possible white pine line tree.

Corner lies in open marsh.

Corner placed and witnessed January 15, 1958.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 1/21/58