

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50. NR. 6 W. . .

Chippewa COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 10-11-14-15

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	12" Red Pine	N 38° E	62 links
		"S 11 NBT"	
	14" Red Pine	S 63° E	51 links
		"S 14 NBT"	
	15" Red Pine	N 30° W	53 links
		"S 10 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one jack pine B.T. bearing S 80° E 39 links. "B.T." in fair condition.

Post in place set by B. McTiver, District Forester.

Corner lies on top of narrow sand ridge.

NOTE: Gov't notes indicate N 80° E 39 links for this B.T.

Corner placed and witnessed January 16, 1958.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 1/16/58
REGISTERED LAND SURVEYOR