

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 6W


Chippewa COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 27, 28, 33 and 34.

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-14-63 Evidence found and corner set with Ray Norkali, District Forester.

WITNESSES TO CORNER..... 14" Red Pine (S. 34 N.B.T.) S. 89° E., 44 Lks.



CIRCLE CORNER REGISTERED

15" W. Pine (S. 33 N.B.T.) S. 80° W., 57 Lks.

12" Red Pine (S. 27 N.B.T.) N. 2° E., 60 Lks.

AND

Placed location Poster 4.00 Chs. South on Road.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-placed from one W. Pine Stump bottom bearing S. 42° E., 24 Lks.  
Found old stub blazed facing Corner. Also found an original Red  
Pine line tree (down) 6.07 Chs. East of Corner and a Red Pine Line  
tree 2.40 Chs. North of Corner, this is a burnt stub with axe marks  
on North side. Both distances check with Record Notes.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1/27/64  
REGISTERED LAND SURVEYOR