

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

Four Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	9-Sec.27 14-Sec.27
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>50</u> N. <u>36</u> S. _____ R. <u>6</u> E. _____ W. _____	13A-Sec.27 14A-Sec.27
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8-8 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9-Sec.27 East 1/16 Corner, Section 27.
- 14-Sec.27 South 1/16 Corner, on East side, Section 27.
- 13A-Sec.27 Corner 666.1' South of the South-East 1/16 Corner, Section 27.
- 14A-Sec.27 Corner 667.15' South of the 1/16 Corner on East side, Section 27.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9-Sec.27 Placed corner midway bet. Center of Section and the East $\frac{1}{4}$ Corner.
- 14-Sec.27 Placed corner midway bet $\frac{1}{4}$ Cor. to North and Sec. Cor. to South.
- 13A-Sec.27 Placed Corner midway bet SE $\frac{1}{16}$ Cor. to North and 1/16 Cor. to South.
- 14A-Sec.27 Placed corner midway bet. 1/16 Cor. to North and Sec. Cor. to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

- 9-Sec.27 Bearings: 9" R. Pine, N57°W, 32.4' and 6" J. Pine, N60°E, 12.3'
- 14-Sec.27 Bearings: 12" Twin R. Pine, S50°W, 1.5' and 14" R. Pine, N27°W, 23.4'
- 13A-Sec.27 Bearings: 8" Oak, S69°W, 22.3' and 7" Oak, S22°E, 30.7'
- 14A-Sec.27 Bearings: 6" Cedar, N62°W, 8.8' and 6" Cedar, S11°W, 23.5'
Corner lies 18' West of an old woods road.

SIGNED BY Billy D. Buckler DATE 10-30-74
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____