

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 6 E.	I-9
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9/7 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Sec. Cor. 22-23-26-27, originally set by Wells Burt, D.S. in 1849.

Bearings were:
Pine 18" N50°W 1.03 chs.
Pine 6" S17°E 22 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Sec. Cor. replaced from one original witness. Found remains of 18" Pine stub, N50°W, 1.03 chs., with partial face and notch in evidence. Chained distance from this corner to original corners, ½ mile West and ½ mile North. Distance checks well.

Found a spruce stake, 14.4' South and 1.0' East of the correct corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at corner.

New Bearings:
10" Red Pine N80°E 14.7'
7" Red Pine S24°E 40.1'

Billy D. Buckler
Billy D. Buckler

SIGNED BY _____ DATE 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8387 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____